

Primary Resource Information: **Single Dwelling**, **Stories 1.50**, **Style: Other, ca 1870** July 2006: This currently abandoned 1½-story, 2-bay, frame dwelling was constructed in at least three sections. The modest house originally began as a 1-bay, 1½-story unit made up of the northern most part of the current dwelling. This would have included the current interior brick flue located within the steeply-pitched gabled roof. The front of the house was enlarged to its current configuration of two bays and then extended to the rear with a 1-story gable end wing and a side shed-roofed lean-to. The original weatherboard siding is visible beneath the current T-111 siding and the roof is now clad in asphalt shingles. None of the windows appear original and include jalousie windows with missing glass in the ½-story, boarded windows on the front and also on the rear wings, and modern 1/1 and 4/4-sash on the side elevation. Few details are evident as the house has been mothballed.



Primary Resource Information: **Single Dwelling**, **Stories 1.00**, **Style: Other, ca 1954** July 2006: Constructed in the mid-1950s, the house is sited perpendicular to the street. The 1-story, 3-bay, gable-end, frame dwelling rests on a concrete block foundation, with exposed rafter ends, new vinyl 1/1-sash windows, asphalt shingle roofing, asbestos siding, and a three-part bay window on the façade.



Primary Resource Information: **Single Dwelling**, **Stories 1.00**, **Style: Other, ca 1957** July 2006: Constructed in 1957, the house is sited perpendicular to the street. The 1-story, 1-bay, hip-roofed concrete block dwelling features a hipped roof, overhanging eaves, exposed rafter ends, an interior concrete block flue, steel casement windows with brick sills, and a side lean-to entrance bay with a shed-roofed hood supported by modern metal posts.



Primary Resource Information: **Single Dwelling**, **Stories 2.00**, **Style: Other, ca 1900** July 2006: This late-19th-century, 2-story, 2-bay, hip-roofed, side-passage-plan, vernacular frame dwelling features a hipped roof with a projecting front cross gable. The roof is clad in asphalt shingles and a central brick chimney pierces it. The frame walls are covered in stucco, the vinyl-clad windows are replacement 6/6-sash, and the house has a plain friezeboard, gable-end returns, a transom over the front door, and a 3-bay hip-roofed front porch with square posts and a modern wooden balustrade. A 2-story wing extends to the rear.



Primary Resource Information: **Single Dwelling**, **Stories 2.00**, **Style: Other, ca 1875** July 2006: This 2-story, 2-bay, hip-roofed vernacular brick dwelling is laid in 6-course American bond. Architectural evidence suggests it was constructed ca. 1870 and it appears on the 1877 Gray's New Map of the area. The house has a full basement in the rear, taking advantage of the banked site. The side-passage-plan dwelling is double-pile and features overhanging eaves, 2/2-sash wood windows with brick jack arches over the first-floor openings, and a central brick flue. The 3-bay hip-roofed front porch has square posts on low stone piers as supports, a modern wooden cross-rail balustrade, and a solid stone foundation.



Primary Resource Information: Multiple dwelling, Stories 2.00, Style: Other, ca 1925

July 2006: This 2-story, 4-bay, shed-roofed, gable-roofed, stuccoed frame duplex was constructed ca. 1925. The symmetrical building is comprised of two front entrances: the door is located on the end bay and a 2/2-sash window on the interior bay next to it. Each of these two bays are sheltered by a 2-bay shed-roofed porch with turned posts, plain balusters, and a side entrance. Architectural details include a parged split-level foundation, overhanging eaves, exposed rafter ends, modern vinyl 2/2-sash windows, and a central flue.



Primary Resource Information: **Single Dwelling**, **Stories 1.50**, **Style: Other, ca 1870** July 2006: Although this 1½-story, 2-bay, frame house is partially obscured by debris in the yard it retains much of its original integrity and appears to date to the late 19th century. It features an exterior brick chimney on the south elevation. The walls are clad in stucco and the gabled roof sheathed in rolled asphalt roofing. The eaves are deeply overhanging with exposed purlin ends. Four-light attic windows are located in the west end and a full-height 4/2 window is in the east gable end. The primary entrance of the building is now along the south side through a 1-story shed-roofed concrete block addition, although this does not appear to be the original entrance into the house. A 1story shed-roofed wing is located along the north side.



Primary Resource Information: **Single Dwelling**, **Stories 1.00**, **Style: Other, ca 1910** July 2006: This 1-story, 2-bay, gable-end, frame building was constructed ca. 1910 and features a raised brick foundation, vinyl siding, asphalt shingle roofing, new vinyl 1/1-sash windows and vinyl shutters, a central brick flue, and a side, 1-story, lean-to. The central front door is sheltered by a shed-roofed hood supported by wooden brackets. A 1-story wing with an interior flue is located in the rear as well as a modern deck with pergola.



Primary Resource Information: **Single Dwelling**, **Stories 1.00**, **Style: Other, ca 1890** July 2006: This 1-story, 3-bay, frame vernacular dwelling is clad in board-and-batten siding and has an asphalt-shingled gabled roof. Constructed ca. 1890, the house rests on a brick foundation, and features 6/6-sash windows, overhanging eaves, vinyl louvered shutters, and a 1-bay, shed-roofed front porch with square posts. A rear shed-roofed wing contains an interior brick flue.



Primary Resource Information: **Single Dwelling**, **Stories 2.00**, **Style: Other, ca 1855** July 2006: This 2-story, 3-bay, brick I-house with a central-front gable is believed to have been constructed in the mid-1850s by Chiles M. Brand. The front brick walls are laid in a 7-course Flemish bond variant and the side and rear brick walls and foundation in 7-course American bond. A mild Victorian interpretation of a vernacular I-house, the dwelling features a gabled roof of standing-seam metal, deeply overhanging eaves, and two interior-end brick chimneys. The house rests on a split-level brick foundation and that is full height in the rear. A large 2-story, hip-roofed, rear brick wing laid in 7-course American bond was constructed in the early 1920s. The house features 1/1-sash windows, a transom over the front door, and a 4-light basement window on the south side. The 3bay, hip-roofed front porch has Tuscan columns and a plain balustrade.



Primary Resource Information: **Single Dwelling**, **Stories 2.00**, **Style: Other**, **2005** July 2006: Constructed in 2005, these six similar, 2-story, cross-gable-roofed frame cottages feature a projecting front cross gable. Very similar in design, they are clad in Hardi-plank siding, roofed in asphalt shingles and feature overhanging eaves, vinyl 2/2sash windows, and shed-roofed hoods supported by wooden brackets over the front entries. They are similar to the set of cottages on the other side of 5th Street. The cottages located directly along 5th Street is three stories in height with a raised basement level.

Individual Resource Status:Single DwellingNon-ContributingTotal:1Individual Resource Status:Single DwellingNon-ContributingTotal:1



Primary Resource Information: Single Dwelling, Stories 1.50, Style: Bungalow/Craftsman, ca 1925

July 2006: This ca. 1925, 1¹/₂-story, 3-bay, Craftsman bungalow is of stone construction and features a hipped roof clad in asphalt shingles with a front and rear hip-roofed attic dormers that contain 6-light attic windows. Architectural details include single and paired 2/2 sash windows, overhanging eaves, exposed rafter ends, 3-light basement windows, concrete sills, and a large interior stone chimney on the south side that pierces through the eaves. A 3-bay, shed-roofed front porch features square stone posts and the rear shedroofed porch is screened in.



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, 2005** July 2006: Constructed in 2005, these six similar, 2-story, cross-gable-roofed frame cottages feature a projecting front cross gable. Very similar in design, they are clad in Hardi-plank siding, roofed in asphalt shingles, and feature overhanging eaves, vinyl 2/2sash windows, and shed-roofed hoods supported by wooden brackets over the front entries. They are similar to the set of cottages on the other side of 5th Street.

Individual Resource Status:	Single Dwelling Non-Contributing Total:1			
Individual Resource Status:	Single Dwelling Non-Contributing Total:1			
Individual Resource Status:	Single Dwelling Non-Contributing Total:1			
Individual Resource Status:	Single Dwelling Non-Contributing Total:1			
Individual Resource Status:	Single Dwelling Non-Contributing Total:1			
Individual Resource Status:	Single Dwelling Non-Contributing Total:1			



Primary Resource Information: Multiple Dwelling, Stories 2.00, Style: Other, ca. 1972

July 2006: Constructed in 1972, this 2-story, 9-bay, gable-roofed building contains nine townhouse units. Each is marked by a door and window bay and they open up to the parking area along the north side of the building. The walls are brick-veneered and the roof is clad in asphalt shingles. The 1x1 windows are sliding metal casements.



Primary Resource Information: Single Dwelling, Stories 2.00, Style: Other, ca 1915
July 2006: This 2-story, 2-bay, side-passage-plan, vernacular dwelling features a hipped roof with a front cross gable and was constructed ca. 1915. The frame walls are clad in stucco and the roof is covered in asphalt shingles. Architectural details include a louvered attic vent, overhanging eaves, plain friezeboard, and 2-bay hip-roofed front porch with square posts on brick piers and a brick porch floor. The 1/1-sash vinyl windows and metal front door are modern alterations. A 2-story, shed-roofed wing extends to the rear. Individual Resource Status: Single Dwelling Contributing Total:1



Primary Resource Information: Mixed:Commerce/Domestic, Stories 3.00, Style: Other, 2006

July 2006: This 3-story, gable and hip-roofed modern building has a commercial use on the first floor and condos on the upper floors. Three levels of metal balconies run along the zig-zag-shaped north façade. The building, which is clad in Hardi-plank board-and-batten, is painted purple, and was constructed in 2006.

Individual Resource Status: Mixed:Commerce/Domestic Non-Contributing Total:1



Primary Resource Information: **Single Dwelling**, **Stories 2.00**, **Style: Other, ca 1860** July 2006: This 2-story, 3-bay, gable-roofed, stuccoed vernacular dwelling features a 2story, bi-level, pedimented entrance porch with decorative vergeboard. Believed to have been constructed ca. 1854-1864 by John T. Barksdale the single-pile symmetrical dwelling rests on a low foundation and has an asphalt shingled roof. The deeply overhanging eaves have a scalloped vergeboard on all sides. To the rear are a 2-story shed-roofed wing with a central brick flue and a rear 1-story shed-roofed wing. The 2story, 1-bay front porch has square supports and a modern exterior stair allowing for access to the second-floor central door and porch. All the 2/2-sash windows have been replaced with modern 1/1-sash.

Individual Resource Status:	Single Dwellin	ng Contributing	Total:1
Individual Resource Status:	Garage	Non-Contributing	Total:1
Individual Resource Status:	Single Dwellin	ng Contributing	Total:1
Individual Resource Status:	Single Dwellin	ng Contributing	Total:1



Primary Resource Information: **Single Dwelling**, **Stories 2.00**, **Style: Other, ca 1915** July 2006: This 2-story, 3-bay, hip-roofed, asymmetrical vernacular dwelling features a central pedimented front gable. The house rests on a parged foundation with vinyl siding and asphalt shingle roofing. The 1/1-sash and 6/6-sash vinyl windows are modern. The 1-bay shed-roofed front porch has battered square posts on vinyl-covered piers and a solid vinyl balustrade. The porch has a segmental-arched bay and is supported on a brick pier foundation with lattice between. Other details include overhanging eaves, and a rear partially enclosed rear porch.



Primary Resource Information: Single Dwelling, Stories 2.00, Style: Other, ca 1900 July 2006: This 2-story, 2-bay, side-passage-plan, vernacular dwelling features a hipped roof with a front cross gable and was constructed ca. 1900. The frame walls are clad in stucco and the roof is covered in asphalt shingles. Architectural details include overhanging eaves, a plain friezeboard, gable-end returns, sidelights around the front door, 4/1-sash windows, and a 3-bay hip-roofed front porch with square posts on stuccoed square piers. A 1-story, shed-roofed enclosed porch is located in the rear. Individual Resource Status: Single Dwelling Contributing Total:1



Primary Resource Information: **Single Dwelling**, **Stories 2.00**, **Style: Other, ca 1900** July 2006: This 2-story, 2-bay, side-passage-plan vernacular brick dwelling is laid in 7-course American bond and features a hipped roof with lower cross gables and a rear gable dormer. The well-preserved Victorian-detailed dwelling, constructed ca. 1900, features penciled mortar joints under the porch, a low brick foundation, a 2-light transom with a segmental arch over the front door, basement windows, and a central-front gable with wooden fishscale shingles and an attic window. The 3-bay, hip-roofed front porch has Tuscan column supports and a denticulated cornice. Other architectural details include a large central brick chimney that has been partially parged, a plain wooden frieze, overhanging eaves, wooden shingles and a 4-light attic window in the side cross gable, and a wraparound, partially enclosed side and rear 1-story porch.



Primary Resource Information: **Single Dwelling**, **Stories 2.00**, **Style: Other, ca 1900** July 2006: This 2-story, 2-bay, side-passage-plan, vernacular dwelling features a hipped roof with a 7-bay wraparound front porch. Constructed ca. 1900, the frame walls are clad in stucco and the roof is covered in asphalt shingles. Architectural details include overhanging eaves, modern 1/1 windows, a rear cross-hipped wing with an enclosed shed-roofed porch and modern rear deck. The 7-bay porch features stuccoed posts and round-arched stuccoed bays.



Primary Resource Information: **Single Dwelling**, **Stories 1.00**, **Style: Other, ca. 1973** July 2006: This 1-story, 4-bay, gable-roofed, brick and board-and-batten vernacular dwelling was constructed in 1973 and features 8/8-sash windows, Texture T-111 siding in the gable ends, and an integral 3-bay front porch.



Primary Resource Information: Single Dwelling, Stories 1.50, Style: Colonial Revival, ca 1925

July 2006: This eclectic 1¹/₂-story, 2-bay stuccoed bungalow has a jerkinhead roof with a large shed-roofed side dormer. Constructed ca. 1925, the frame walls are clad in stucco, the foundation is parged, and the roof covered in asphalt shingles. Architectural details include single and paired 4/1 windows, wooden triangular brackets supporting the overhanging eaves, exposed rafter ends, 3-light basement windows, a gable-hood entry supported by triangular brackets, and a partially engaged corner porch with triple Tuscan column supports and a modern wooden railing.



Primary Resource Information: **Single Dwelling**, **Stories 2.00**, **Style: Other, ca. 1870** July 2006: This 2-story, 3-bay, brick I-house with a central-front gable is believed to have been constructed before 1876 when it was sold by John N. Fry to John and Rebecca Shelton, who were living in the house at that time. Architecturally the house appears to have been constructed ca. 1870. The front brick walls are laid in a 7-course-American-with-Flemish-bond and the side and rear brick walls and foundation in 7-course American bond. A Victorian interpretation of a vernacular I-house, the dwelling features a bellcast gabled roof of standing-seam metal, deeply overhanging bracketed eaves, and a projecting polygonal bay window on a brick foundation. The bay window and the 1-bay front porch, which has modern metal supports and a bracketed cornice, both have Mansard roofs. The 2/2-sash windows, two semi-exterior-end brick chimneys that break through the eaves, the 5-light transom and 3-light sidelight around the front door and the basement windows all appear original. A 1-story frame wing on raised basement extends the full width of the rear of the house and appears to have been constructed in several sections.

Individual Resource Status:	Single Dwelling Contributing	Total: 1
Individual Resource Status:	Shed Non-Contributing	Total: 1
Individual Resource Status:	Shed Non-Contributing	Total: 1



Primary Resource Information: **Single Dwelling**, **Stories 2.00**, **Style: Other, ca 1895** July 2006: This large, rambling, 2-story, 2-bay, Victorian dwelling features a hipped roof with lower cross gables and appears to have been recently renovated. All the 1/1-sash windows as well as the full-light doors are modern replacements. The roof has been covered in asphalt shingles and the chimneys removed. The brick foundation, overhanging eaves, gable-end returns, weatherboarded exterior walls with corner boards, and square wooden shingles and Gothic-arched attic windows in the gable ends appear original. The house features a 7-bay wraparound porch with a corner entry, turned posts and plain pickets. The 2-story cross-gable-roofed rear wing has similar detailing to the front portion.

Individual Resource Status:	Single 1	Dwelling Contributing	Total:1
Individual Resource Status:	Shed	Non-Contributing	Total:1





Primary Resource Information: **Single Dwelling**, **Stories 2.00**, **Style: Other, ca 1895** July 2006: This 1890s, 2-story, 2-bay, cross-gable-roofed, side-passage-plan, vernacular frame dwelling features a projecting front cross gable. The roof is clad in standing-seam metal while the walls have been covered with aluminum siding. Because of the sloped site, the parged foundation is split-level. A parged chimney toward the rear of the building was observed. The 2/2-sash windows, plain friezeboard, gable-end returns, front-entry transom, and 2-bay front porch with Tuscan columns and plain balustrade appear original. To the rear is a 1-story wing.



Primary Resource Information: **Single Dwelling**, **Stories 2.00**, **Style: Other, ca 1900** July 2006: This ca. 1900, 2-story, 2-bay, gable-roofed side-passage-plan dwelling is currently vacant and boarded up. The walls are clad in aluminum siding, the roof is covered in asphalt shingles, the cornices have gable-end returns, and a transom is located above the front door. The windows and doors have been covered in plyboard. A 2-story wing extends to the rear. The 2-bay, hip-roofed front porch has square posts and a solid concrete balustrade that extends beyond the porch roof.

307¹/₂ 5th Street SW 104-0213-0181



Primary Resource Information: Mixed:Commerce/Domestic, Stories 2.00, Style: Other, ca 1900

July 2006: This ca. 1900, 2-story, 3-bay, gable-end frame building is clad in aluminum siding on the façade and stucco on the sides and rear. The windows and door on the first floor are all modern replacements and suggest that the front originally had a storefront or some other type of opening. The gable-end front features gable-end returns and a boxed cornice. The side elevation shows a plain frieze and original 2/2-sash windows. To the rear is a 2-story shed-roofed wing with a set of modern exterior stairs leading to a second-story apartment.

Individual Resource Status: Mixed:Commerce/Domestic Contributing Total:1



308 5th Street SW 104-0213-0164

Primary Resource Information: Single Dwelling, Stories 2.00, Style: Other, ca 1890 July 2006: This late-19th-century, 2-story, gable-roofed dwelling is one of three almost identical houses sited next to each other on 5th Street. They are comprised of a 2-bay main block with an exterior-end brick chimney and have a slightly recessed, 1-bay, 1- or 2-story side wing off the side with the chimney. This house is clad in stucco, roofed in standing seam metal, and features overhanging eaves, 6/6-sash windows, and multiple rear 1-story wings. The 4-bay hip-roofed front porch, which has stuccoed square posts, a solid balustrade, and wooden steps and handrail, unites both front sections of the house. Individual Resource Status: Single Dwelling Contributing Total:1



Primary Resource Information: **Single Dwelling**, **Stories 2.00**, **Style: Other, ca 1900** July 2006: This 2-story, 2-bay hip-roofed vernacular dwelling has a cantilevered second floor over an enclosed first floor porch that has two doors and lattice-covered walls. The second floor is clad in stucco and the roof with overhanging eaves is covered in standing-seam metal. The 1/1 windows are modern and the house appears to have a 2-story rear lean-to addition.



Primary Resource Information: **Single Dwelling**, **Stories 2.00**, **Style: Other, ca 1890** July 2006: This late-19th-century, 2-story, gable-roofed dwelling is one of three almost identical houses sited next to each other on 5th Street. They are comprised of a 2-bay main block with an exterior-end brick chimney and have a slightly recessed, 1-bay side wing off the side with the chimney. This house is the only one of the three with a 1-story side wing: the others have a 2-story side wing. This house, clad in vinyl siding with an asphalt shingled roof, features a parged brick chimney, overhanging eaves, 6/6-sash windows, and multiple rear 1-story wings. The 4-bay hip-roofed front porch, which has square posts, a plain balustrade, and concrete steps, unites both front sections of the house.



Primary Resource Information: Mixed:Commerce/Domestic, Stories 2.00, Style: Other, ca 1900

July 2006: This 2-story, 3-bay, shed-roofed brick building was constructed at the turn-ofthe century. Commercial use was on the first floor and living space on the second, as was common with many commercial buildings of this era in urban areas. The three-part wooden storefront topped by a denticulated and bracketed entablature is intact and is comprised of large, fixed, 4-light, wood windows over paneled reveals flanking a doubleleaf, wood and glass door. The second floor facade is comprised of three, unevenly spaced, 1/1-sash windows with segmental arches. Two of the windows are centered above the storefront and the third is centered above the blank wall on the first floor, which may have at one time contained a door leading to a second-story stair. The building also features a corbelled brick cornice with overhanging wood entablature, a shed roof, a split-level brick foundation, two interior brick chimneys, and a modern rear deck. The building is now only used residentially.

Individual Resource Status: Mixed:Commerce/Domestic Contributing Total:1



Primary Resource Information: **Single Dwelling**, **Stories 2.00**, **Style: Other**, **ca 1895** July 2006: This late-19th-century, 2-story, gable-end dwelling is one of three almost identical houses sited next to each other on 5th Street and is the best preserved. They are comprised of a 2-bay, gable-end main block with an exterior side brick chimney and each has a slightly recessed, 1-bay side wing off the side with the chimney. The wing has a side gable roof. This house is one of two with a 1-story side wing: the other has a 2-story side wing. The second floor has only a one bay, which is centered in the gable end and is located above the first-floor window. Clad in vinyl siding with an asphalt-shingled roof, the house features a parged brick chimney, overhanging eaves, 2/2-sash wood windows, exposed rafter and purlin ends, a Craftsman-style door, a scroll bracket in the front gable end, and a side 1-story gable-roofed wing with a side wing. The 1-bay hip-roofed front porch, which has rectangular stuccoed posts, a solid balustrade, and a round-arched bay, runs the full width of the main block.



Primary Resource Information: **Single Dwelling**, **Stories 2.00**, **Style: Other, ca 1900** July 2006: This late-19th-century, 2-story, gable-end dwelling is one of three almost identical houses sited next to each other on 5th Street. They are comprised of a 2-bay, gable-end main block with an exterior side brick chimney and each has a slightly recessed, 1-bay side wing off the side with the chimney. The wing has a side gable roof. This house is the only one with a 2-story side wing: the other 2 have 1-story side wings. The second floor has only a one bay, which is centered in the gable end and is located above the first-floor window. Clad in stucco with an asphalt-shingled roof, the house features a brick chimney, overhanging eaves, modern 1/1-windows, some original 2/2-sash windows, modern vinyl shutters, and a side porch off the side wing. The 2-bay hiproofed front porch has paneled square posts as supports and runs the full width of the main block.





Primary Resource Information: **Single Dwelling**, **Stories 2.00**, **Style: Other, ca 1890** July 2006: This late-19th-century, 2-story, gable-roofed dwelling is one of three almost identical houses sited next to each other on 5th Street. They are comprised of a 2-bay main block with an exterior-end brick chimney and have a slightly recessed, 1-bay, 1- or 2-story side wing off the side with the chimney. This house is clad in stucco, roofed in standing asphalt shingles, and features overhanging eaves, modern 1/1-sash windows, and a rear 1-story wing. The 2-bay hip-roofed front porch, which has stuccoed square posts, and a solid balustrade, only covers the main block of the house.



Primary Resource Information: Single Dwelling, Stories 2.00, Style: Other, ca 1895 July 2006: This late-19th-century, 2-story, gable-end dwelling is one of three almost identical houses sited next to each other on 5th Street. They are comprised of a 2-bay, gable-end main block with an exterior side brick chimney and each has a slightly recessed, 1-bay side wing off the side with the chimney. The wing has a side gable roof. This house is one of two with a 1-story side wing: the other has a 2-story side wing. The second floor has only a one bay, which is centered in the gable end and is located above the first-floor window. Clad in vinyl siding with an asphalt-shingled roof, the house features a parged brick chimney, overhanging eaves, modern 1/1-windows, a small scroll bracket in the front gable end, and a side 1-story gable-roofed wing. The 1-bay gabled front porch has battered columns on prick piers and runs the full width of the main block. *Individual Resource Status:* Single Dwelling Contributing Total:1



Primary Resource Information: **Single Dwelling**, **Stories 2.00**, **Style: Other, ca 1890** July 2006: This 2-story, 2-bay, side-passage-plan vernacular dwelling features a shed roof with a small bracketed parapet. The house rests on a brick foundation, the walls are clad in asbestos shingles, and the roof is covered in standing-seam metal. The 2/2-sash windows appear original while the front door is a modern replacement. To the rear is a 1-story wing. The 3-bay front porch features Tuscan columns, plain balusters, and a hipped roof.



Primary Resource Information: Single Dwelling, Stories 2.00, Style: Other, ca 1890
July 2006: This 2-story, 2-bay, gable-roofed with a central-front gable frame dwelling
was constructed ca. 1890. Neither the two bays nor the front gable are centered within the façade, giving the building an interesting appearance. The stuccoed house has modern
1/1-sash windows, a new bay window on the front, a standing-seam metal roof,
overhanging eaves, a new front door, a rectangular attic vent in the central front gable, a
rear 2-story wing with side entrance and porch, and a 3-bay front porch with square posts.
Individual Resource Status: Single Dwelling Contributing Total:1





Primary Resource Information: **Single Dwelling**, **Stories 2.00**, **Style: Other, ca 1910** July 2006: This currently vacant, ca. 1910, 2-story, 2-bay, hip-roofed, side-passage-plan, vernacular frame dwelling features an asphalt shingled roof, overhanging eaves, 1/1 vinyl windows (the first–floor openings have been boarded up), a parged foundation, Hardiplank siding, a 2-story rear shed-roofed wing, and a 3-bay front porch with turned posts and a modern balustrade.



Primary Resource Information: **Single Dwelling**, **Stories 1.00**, **Style: Other, ca 1950** July 2006: This 1-story, 3-bay, concrete block vernacular dwelling appears to have been constructed around 1950. It has a hipped roof, clad in asphalt shingles, with overhanging eaves, exposed rafter ends, and an interior concrete block flue. The paired windows are 6/6-sash and the house has a split-level foundation that opens to a full basement level on the south side. Several rear additions have been made to this house making it quite large. A number of exterior doors suggest that it may have been divided into several living units. The large, pedimented, 3-bay front porch has square columns, a solid balustrade, and an aluminum awing.



Primary Resource Information: **Single Dwelling**, **Stories 2.00**, **Style: Other, ca 1890** July 2006: This 2-story, 2-bay, gable-roofed with a central-front gable frame dwelling was constructed ca. 1890. Neither the two bays nor the front gable are centered within the façade, giving the building an interesting appearance. The stuccoed house has 2/2-sash windows, asphalt shingled roofing, a 6-light transom and sidelights around the front door, an exterior brick chimney along the rear gable side, overhanging eaves with exposed rafter ends, and a plain friezeboard. The 1-story, gable-roofed, stuccoed rear wing has a side lean-to, a basement entry, and an exterior-end concrete block flue. The 3-bay, hiproofed front porch has square stuccoed supports that form segmental-arched bays, and a solid balustrade.



Primary Resource Information: **Single Dwelling**, **Stories 2.00**, **Style: Other, ca 1955** July 2006: Constructed ca. 1955, this 2-story, 3-bay, gable-roofed vernacular dwelling is of concrete block construction on the first floor and frame that has been stuccoed on the second floor. The roof is clad in asphalt shingles and features a central concrete block flue. The windows are 6/6-sash and the house has overhanging eaves, exposed rafter ends, and porches on three sides.

418 5th Street SW 104-0221 Other DHR Id #: 104-0213-0168



Primary Resource Information: Single Dwelling, Stories 1.00, Style: Federal, ca 1832

July 2006: Constructed in 1832, the left three bays of this 1-story brick dwelling are original and follow a side-passage plan. The exterior brick chimney that was originally on the south end of the house was incorporated into the side 1-bay 1-story brick wing that was added in 1892. The walls of the wing were built around the chimney with the exception of the area above the roof level, thus not having to disturb attic windows in the gable end of the original section. The original 3-bay asymmetrical section is laid in Flemish bond brick on the façade and 5-course American bond on the sides and rear. The mousetooth brick cornice, 6-panel front door with architrave trim, 6/6-sash windows, and parged brick foundation are all in good condition. The side brick wing is laid in 7-course American bond, typical of its late-19th century period, but has a matching mousetooth cornice. A rear 1-story frame wing on a brick foundation appears to be a modern addition yet blends in with the rest of the house.



Primary Resource Information: **Single Dwelling**, **Stories 1.00**, **Style: Other, ca 1940** July 2006: Constructed ca. 1940, this 1-story, 3-bay, gable-end vernacular dwelling is clad in asbestos shingle and has an asphalt-shingled roof. The house rests on a concrete block foundation and features 6/6-sash windows, overhanging eaves, a full size attic window in the front gable end, exposed rafter ends, a central interior brick chimney, and a 3-bay shed-roofed front porch with square posts and plain pickets.



Primary Resource Information: Foundation,

July 2006: This site includes a rectangular concrete block foundation that is currently under construction on this site. The floor joists have not yet been set but the metal vents are in (NC Site).

Individual Resource Status: Foundation Non-Contributing Total:1