

808 Cherry Avenue 104-0213-0059



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1900**
July 2006: This 2-story, 3-bay frame I-house features a central-front gable, a brick pier foundation with infill, a standing-seam metal roof, and T-111 siding over the original weatherboard siding that is still evident in the front gable end and the rear of the house. It appears that the 2/2-sash windows on the first floor are replacement windows while the second-story ones are original. Other architectural details include a 2-light transom over the front door, an exterior-side brick chimney on the rear gable, and a 3-bay hip-roofed front porch with square posts, sawn brackets, and turned balusters. To the rear is a 1-story, gable-roofed frame wing.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

Individual Resource Status: **Shed** Contributing *Total:* 1



Primary Resource Information: **Single Dwelling, Stories 1.50, Style: Other, ca 1925**

July 2006: This 1 ½-story, 2-bay, vernacular, gable-roofed frame cottage has a small shed-roofed front dormer with 6-light windows, an exterior-end brick chimney, overhanging eaves, 6/6-sash windows, and paneled wooden shutters pierced with the silhouette of a pine tree. The entrance is located in the southwest corner of the house, under the recessed porch that is fronted by a 1-bay pedimented portico supported by square posts. To the side is a shed-roofed second-story wing supported by posts. To the rear is a shed-roofed 1-story wing. The house is clad in vinyl siding and the roof covered in asphalt shingles.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

Individual Resource Status: **Garage** Contributing *Total:* 1

913 Cherry Avenue 104-0213-0047



Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Other, ca 1950**
July 2006: This 1-story, 3-bay, vernacular frame dwelling was constructed ca. 1950 and features asbestos siding, a gabled roof clad in asphalt shingle, and a pedimented 2-bay front porch with square posts and plain pickets. The split level foundation is of concrete block and no chimney was visible.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

915 Cherry Avenue 104-0213-0273



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1900**

July 2006: This 3-bay, 2-story, gable-roofed, ca. 1900, frame I-house features a 2-story projecting central-front gable and rests on a parged foundation. The gable-end returns, 4-light transom and 3-light sidelights around the front door, and the 5-bay front porch with turned posts, plain balusters, and sawn brackets appear original. The 6/6 vinyl windows are replacements as is the vinyl siding, and asphalt shingle roof.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

Individual Resource Status: **Garage** Non-Contributing *Total:* 1



Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Gothic Revival, ca 1891**

July 2006: Constructed ca. 1891, this 1-story, L-shaped frame dwelling features some Gothic Revival-style detailing. Originally clad in weatherboard, the exterior walls are now covered in asbestos shingle and the cross-gabled roof in asphalt shingle. The house has steeply pitched roofs with deeply overhanging eaves and a plain frieze and a large central parged chimney. A pointed-arched attic vent is located in each of the cross gables. The original 4/1 sash windows are intact except in the front cross gable where one has been replaced with a single-light sash. A 2-bay wraparound porch with square posts and plain pickets leads to the front entrance door. To the rear is a 1-story gable-roofed wing and shed-roofed wings that are on raised foundations due to the sloped rear yard.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

919 Cherry Avenue 104-0213-0271



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1900**
July 2006: This 2-story, 2-bay hip-roofed, frame dwelling features a central brick chimney, a parged foundation, a standing-seam metal roof, a transom over the door, and an enclosed 3-bay front porch with Tuscan columns and turned balusters. Constructed ca. 1900, the building is now clad in aluminum siding and has replacement vinyl 2/2 windows. A frame wing extends to the rear.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

Individual Resource Status: **Garage** Non-Contributing *Total:* 1

921 Cherry Avenue 104-0213-0270



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1900**
July 2006: This 3-bay, 2-story, hip-roofed, frame I-house features a central-front gable, brick foundation, weatherboard siding and an asphalt shingle roof. The gable-end returns, 2-light transom over the double-leaf door, large interior brick chimney, overhanging eaves with plain frieze, rectangular attic vent, and 3-bay hip-roofed front porch with Ionic columns and denticulated cornice, all appear to be original. To the rear is a 2-story hip-roofed ell and 1-story enclosed porch.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

923 Cherry Avenue 104-0213-0269



Primary Resource Information: **Multiple dwelling, Stories 2.00, Style: Other, ca 1980**

July 2006: This apartment duplex, constructed in 1980, is a 2-story, 3-bay, gable-roofed building with a rear 2-story wing. Clad in unpainted wood siding and roofed in asphalt shingle, it has 1/1 wood windows, a 1-bay hip-roofed front porch with square posts, and a rear two-story ell with a recessed side entry.

Individual Resource Status: **Multiple dwelling Non-Contributing Total: 1**

1001, 1003 Cherry Avenue 104-0213-0268



Primary Resource Information: **Apartment Building, Stories 2.00, Style: Other, ca 1981**

July 2006: This apartment complex, constructed in 1981, is made up of two, 2-story frame apartment buildings with weatherboard siding, paired 6/1 windows, and a catslide gable roof clad in asphalt shingle. Each has a two-story deck out onto a common green area.

Individual Resource Status: **Apartment Building Non-Contributing Total:1**

Individual Resource Status: **Apartment Building Non-Contributing Total:1**

1005 Cherry Avenue 104-0213-0267



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1900**
July 2006: This turn-of-the-century, 2-story, 2-bay, gable-roofed frame vernacular dwelling has a central door with an enclosed transom and 2-light sidelights. The house is clad in weatherboard siding and features a plain bracketed frieze, a standing-seam metal roof, and an exterior brick chimney on the rear gable side. The 6/6 vinyl windows are modern replacements, one of the second-floor windows has been enclosed, and one bay of the 3-bay front porch with chamfered posts, denticulated cornice and sawn balustrade and brackets has been enclosed. To the rear is 1-story gable-roofed wing with interior brick flue.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

1007 Cherry Avenue 104-0213-0266



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1900**

July 2006: This 2-story, 2-bay, frame vernacular dwelling has a cross-gabled roof clad in standing-seam metal. The walls are covered in vinyl siding and the 6/6 vinyl windows, louvered shutters and front door with sidelights are new. Architectural details include a parged foundation, an exterior side brick chimney, gable-end returns, and 2-bay hip-roofed front porch with turned posts. To the rear is 1-story gable-roofed wing with interior brick flue.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

Individual Resource Status: **Shed** Non-Contributing *Total:* 1

1009 Cherry Avenue 104-0213-0265



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1890**
July 2006: This late-19th-century, 2-story, 3-bay, frame vernacular dwelling features Victorian elements, a shallow Mansard roof, and a 2-story projecting polygonal bay on the end bay of the front façade. The house, clad in asbestos shingle, has a parged foundation, an interior parged brick chimney, 2/2-sash windows, standing-seam metal and asphalt shingle roofing, and a 4-light transom and 3-light sidelights around the front door. The bracketed wood cornice contains pendants and the 4-bay hip-roofed front porch has turned posts supports. The house extends to the rear with a shed-roofed 1-story wing on a raised foundation.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

600 Delevan Street 104-0213-0100



Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Other, ca 1971**
July 2006: Constructed ca. 1960, this 1-story, 3-bay, gable-end concrete block dwelling features steel 4 x4 windows, a central concrete block flue and aluminum siding in the gable end. It is fronted by a 3-bay shed-roofed porch with square posts and a 2-rail balustrade.

Individual Resource Status: **Single Dwelling Non-Contributing** Total: 1

606 Delevan Street 104-0213-0101



Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Other, ca 1960**
July 2006: Constructed ca. 1960, this 1-story, 3-bay, gable-roofed, frame dwelling is clad in weatherboard siding. The original 1-bay gabled front porch has been expanded to three bays with a shed roof, square posts and lattice in the bays. Details include asphalt shingle roof, sliding casement windows, and a central concrete block flue.

Individual Resource Status: **Single Dwelling Non-Contributing** Total: 1

613 Delevan Street 104-0213-0099



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1890**
July 2006: This late-19th-century, 2-story, 2-bay, hip-roofed vernacular dwelling is stuccoed. It features overhanging eaves, and exterior-end brick chimney (fairly modern), a pedimented 1-bay front porch with square posts, and a 1-bay hip-roofed side porch. Some of the single and paired 6/6- and 8/8-sash windows and bay window are replacements. A 1-story shed-roofed wing extends to the rear.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

702 Delevan Street 104-0213-0098



Primary Resource Information: **Mixed:Commerce/Domestic, Stories 2.00, Style: Other, ca 1961**

July 2006: Constructed ca. 1961, this 2-story, 2-bay, gable-end, cinder block building has a commercial (office) use on the first floor and a residential use (two apartments) on the second. A set of metal exterior stairs leads up to the second-story apartments that are fronted with a shed-roofed porch. The gable-end roof is clad in asphalt shingle with board-and-batten in the gable end, and the masonry walls are parged. A three-part bay window is located on the front while the rest of the windows are horizontal 1/1-sash windows. A garage door is located at the northwest, 1st-floor corner of the building.

Individual Resource Status: **Mixed:Commerce/Domestic Non-Contributing Total:1**

318 Dice Street 104-0213-0192



Primary Resource Information: **Multiple dwelling, Stories 1.00, Style: Other, ca 1925**

July 2006: Constructed ca. 1925, this 1-story, 6-bay, stuccoed frame, vernacular duplex is sited perpendicular to the road. It features a hipped roof of asphalt shingle; overhanging eaves with exposed rafter ends; a central brick chimney, 1/1-horizontal wood windows, and a 3-bay shed-roofed front porch with square posts.

Individual Resource Status: **Multiple dwelling** Contributing *Total:* 1

402 Dice Street 104-0213-0191



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1853**
July 2006: This 2-story, 3-bay, brick I-house with a central-front gable is believed to have been constructed ca. 1850, although some of the architectural features suggest a post-Civil War construction date. It is believed to have been one of several dwellings in the area constructed by master builder, Allen Hawkins, whose own house was on 5th Street SW. The front of the gable-roofed dwelling is laid in Flemish-bond brick, while the rear and sides are laid in a 7-course American bond with Flemish bond. The house appears to have been repointed as the mortar joints are very prominent. The foundation is parged, the roof covered in standing-seam metal, and the house features modern 2/2-sash windows (paired in 2nd-story central bay), a 4-light transom and sidelight around the front door, overhanging eaves with a plain bracketed frieze, 2 interior-end brick chimneys, and gable-end returns. The 3-bay, Colonial Revival-style front porch has Tuscan columns and a concrete floor (ca.1979). To the rear is a 1-story brick wing, laid in 8-course American bond with Flemish bond. This service wing has a mousetooth cornice, modern 2/2-sash windows, and a gabled metal roof. A modern 1-story, gable-roofed, stuccoed addition extends south of the rear wing.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

Individual Resource Status: **Shed** **Non-Contributing** *Total:* 1

404 Dice Street 104-0213-0190



Primary Resource Information: **Single Dwelling, Stories 1.50, Style: Bungalow/Craftsman, ca 1935**

July 2006: Constructed ca. 1935, this well-preserved 1 ½-story, 3-bay, stuccoed bungalow features a gable-end roof line with a 1-bay gable-end front porch. The 1-bay front porch has is supported by battered stuccoed piers on a solid balustrade that extends the entire width of the house. The house rests on a parged foundation and features overhanging eaves with exposed rafter ends, an exterior-side brick chimney that breaks through the eaves, 10/1 Prairie-sash windows on the front; a Craftsman-style front door, paired 6/1 sash windows on the sides of the house, an attic window in the front gable end, and an interior brick flue.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

405 Dice Street 104-0213-0193



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1890**
July 2006: Constructed ca. 1890, this large, 2-story, 3-bay, stuccoed frame vernacular dwelling with a cross-gable-roofed, features a large 2-story hip-roofed stuccoed addition on the side/rear. Architectural details include a plain friezeboard with turned vergeboard, a 3-light transom over modern front door, 2/2-sash vinyl windows, round attic vents in the gable ends, a parged foundation, and a fine 8-bay wraparound porch with turned posts, turned spindles, and a spindle frieze.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

406 Dice Street 104-0213-0189



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Gothic Revival, ca 1874**

July 2006: This 2-story, 2-bay, Vernacular Gothic Revival-style frame dwelling was constructed in 1874. The two bays are not centered within the façade, while the prominent central front gable is, giving the building an interesting appearance. The well preserved house has weatherboard siding, a brick pier with infill foundation that has been parged, 6/6-sash wood windows, a central brick flue, a plain friezeboard, overhanging eaves, and a modern front door. To the rear is a 2-story gable-roofed ell and one-story addition. The second-story front windows feature gabled window crowns supported by brackets. The 3-bay front porch has a shallow Mansard roof, turned posts and plain pickets and may have been remodeled as it covers the first-floor window and door hoods.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

409 Dice Street 104-0213-0194



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1910**
July 2006: This ca. 1910, 2-story, 2-bay, hip-roofed, vernacular frame dwelling features an asphalt shingle roof, overhanging eaves, 4/1 windows (some with aluminum awnings), a brick foundation, aluminum siding, an enclosed rear porch, 5-light sidelights around the front door, and a 3-bay front porch with Tuscan column supports and aluminum awnings.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

Individual Resource Status: **Garage** Non-Contributing *Total:* 1

410 Dice Street 104-0213-0188



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1875**
July 2006: The original ca. 1875, section of this dwelling is the 2-story, 2-bay, side-passage-plan portion. The recessed 2-story, 1-bay side wing was constructed ca. 1877, giving it a 3-bay, center-passage form that is united by the 3-bay hip-roofed front porch with turned posts and plain pickets. The house has a gable roof of asphalt shingle, weatherboard siding, a parged stone and concrete foundation, 6/6-sash windows, 2 central brick flues with corbelled caps, overhanging eaves, and a rear 1-story wing.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

412 Dice Street 104-0213-0187



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1880**
July 2006: This late-19th-century, 2-story, 2-bay, side-passage-plan, vernacular dwelling features a gabled roof with central-front gable. The house appears to have been remodeled fairly recently when the siding was replaced with Hardi-Plank, the roofing with asphalt shingle, the windows with vinyl 6/6-sash, and the wooden front door with a metal one. The house features a projecting bay on the first floor with three large 6/6-sash vinyl windows, a brick pier foundation with stone infill, and a 2-bay front porch with turned posts and plain pickets.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

412 ½ Dice Street 104-0213-0195



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 2006**
July 2006: Constructed ca. 2006, this narrow and long, 2-story, 2-bay, modern dwelling features a half-hyperbolic roof, siding made up of large rectangular panels, exposed rafter ends, full-light double-leaf French doors, narrow fixed single-light windows with transom, parapet walls along the side roofline, and a rear deck.

Individual Resource Status: **Single Dwelling Non-Contributing** Total: 1

413 Dice Street 104-0213-0196



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1890**

July 2006: This 2-story, 2-bay, side-passage-plan, vernacular dwelling features a cross-gabled roof with a front cross gable and was constructed ca. 1890. The frame house appears to have recently been remodeled. It features Hardi-plank siding, modern vinyl 6/6-sash windows, a new front door, new turned spindles on the 2-bay hip-roofed front porch, rear 2-story wing, and modern asphalt shingle roofing. The gable-end returns and parged foundation are original.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

414 Dice Street 104-0213-0186



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1894**
July 2006: This ca. 1894, 2-story, 3-bay, side-passage-plan, vernacular dwelling features a shed roof with a parapet with central front gable and a bracketed cornice. The house, which rests on a parged foundation, is clad in stucco on the first floor beneath the porch and board-and-batten siding on the rest of the exterior wall. The windows are 2/2-sash, and the house features a standing-seam metal roof, an enclosed transom over the door, 6/6 windows in the rear, and a 3-bay hip-roofed front porch with square supports and plain pickets.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

416 Dice Street 104-0213-0185



Primary Resource Information: **Slave Quarters, Stories 2.00, Style: Other, ca 1895**
July 2006: This 2-story, 2-bay, side-passage-plan, vernacular dwelling features a cross-gabled roof with a front cross gable and was constructed ca. 1895. The frame house, currently undergoing rehabilitation, is clad in stucco and features a standing-seam metal roof, gable-end returns, a stuccoed foundation, 1/1-sash vinyl replacement windows, a modern front door, and a rear 2-story ell with side addition. The 2-bay hip-roofed front porch, now with square posts, 4-rail balustrade, and asphalt shingle roofing, originally had turned posts supports as evidenced by the turned pilaster near the front door.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

513 Dice Street 104-0213-0010



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Vernacular Greek Revival, ca 1860**

July 2006: Currently under restoration, this house was constructed in 1860 and is a vernacular interpretation of the Greek Revival style. The 2-story, 3-bay, hip-roofed frame I-house rests on a full brick basement laid in 7-course American bond. The walls are clad in weatherboard with a plain frieze and cornerboards, and the shallow-pitched roof is covered in standing-seam metal. The wood windows, including the ones in the basement level, vary in size based on their location and, although modern, have 6/6- double-hung sash. An exterior brick chimney is located at each end: the one on the north is original and has been partially parged, while the one on the south end has recently been rebuilt. Both chimney stacks pierce the eaves of the building. The original front of the house faces west and features 4-light sidelights around the 4-paneled front door. The 1-bay pedimented portico in front of the entrance is supported by Tuscan columns with plain pickets and a wooden stair. Above it on the second floor is a small 6-light window. The house was originally 1½ stories in height.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

598 Dice Street 104-0213-0110



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1900**

July 2006: This 2-story, 2-bay, hip-roofed, vernacular frame dwelling features pedimented front and side gables. Resting on a parged solid foundation, the house is clad in aluminum siding and the roof in asphalt shingle. The house has a 2-story hip-roofed side/rear wing that gives the house an L-shaped configuration. An enclosed one-story three-bay porch is located in the inner angle of the L. Because of the sloped site, the split-level foundation is well above grade on the east side of the house and contains paired 6/6-sash windows and modern basement windows along the north. Other details include 2/2-sash windows, rectangular attic vents in the gable ends, a 2-light transom over the front door, and a bracketed bonnet hood supported by brackets over the front door.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

599 Dice Street 104-0213-0112



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1910**
July 2006: This 2-story, 2-bay, side-passage-plan, vernacular dwelling features a cross-gabled roof and was constructed ca. 1910. The frame house is clad in asbestos shingle and features a standing-seam metal roof, gable-end returns, a brick foundation, a round attic vent, 1/1-sash windows and a 3-bay hip-roofed front porch with Tuscan columns that rest on brick piers and a balustrade comprised of staggered bricks. A 2-story ell extends to the rear and includes enclosed side 2-story porches, two 1-story shed-roofed wings, and a modern rear deck.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

Individual Resource Status: **Single Dwelling Non-Contributing** *Total:* 1

600 Dice Street 104-0213-0109



Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Other, ca 1910**

July 2006: This 2½-story, 4-bay, stuccoed, frame vernacular dwelling currently has two front doors, one of which appears to have been added. A variation on the American Foursquare form, the early-20th-century house features a hipped roof with two central corbelled brick chimneys, hipped dormers on the front and side elevation both with 6/6-sash windows, and overhanging eaves. The plain wooden frieze, 2/2-sash windows, and 6-bay wraparound porch with Tuscan columns and solid tongue-and-groove wood balustrade appear original. The southeast corner of the house contains a bank of 6/6-sash windows that suggest either a sleeping porch or an enclosed integral porch. A rear 2-story wing extends to the rear and contains a garage bay on the first floor end bay and 2-story side porches.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

601 Dice Street 104-0213-0113



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1910**
July 2006: This 2-story, 2-bay, side-passage-plan, vernacular dwelling features a hipped roof with a front cross gable and was constructed ca. 1910. The frame house is clad in vinyl siding and features asphalt shingle roofing, gable-end returns, a brick foundation, 1/1-sash vinyl replacement windows, and a 3-bay hip-roofed screened-in front porch with turned posts. A 2-story ell extends to the rear as well as a 1-story shed-roofed wing.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

602 Dice Street 104-0213-0108



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1910**

July 2006: This 2-story, 2-bay, side-passage-plan, vernacular dwelling features a hipped roof with cross gables and was constructed ca. 1910. The brick house is clad in stucco and features a plain friezeboard, stuccoed foundation, central parged brick flue, 2/2-sash windows, round wooden attic vent, 2-light transom over door, and gable-end returns. The 3-bay front porch features a hipped roof supported by turned posts, with spindle brackets.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1



Primary Resource Information: **Single Dwelling, Stories 1.50, Style: Bungalow/Craftsman, ca 1930**

July 2006: This 1½-story, 2-bay stuccoed bungalow features a clipped gable-end roof line with jerkinhead dormers on the side elevations. The 2-bay front porch has a bellcast Mansard roof and one open segmental-arched bay supported by battered posts on piers. The other bay is enclosed by a bank of four 6/1-sash windows with a masonry window plant box supported by three brackets. The long and fairly narrow house, constructed a. 1930 rests on a cinder block foundation, with 3-light basement windows, and a roof clad in asphalt shingles. The deeply projecting eaves are boxed and the dormers give the impression of half-timbering in the wall treatment. An exterior parged chimney that pierces through the eaves is located along the west side of the house. The single, paired, and triple wood windows are 6/1 sash with the upper sash shorter than the lower sash. The front porch has a stuccoed balustrade and a tiled floor.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

Individual Resource Status: **Garage** Contributing *Total:* 1

605 Dice Street 104-0213-0114



Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Other, ca 1963**
July 2006: Constructed in 1963, this 1-story, 3-bay, gable-roofed vernacular dwelling is constructed of concrete block. The roof is clad in asphalt shingle as is the 1-bay shed-roofed front porch with square posts. The single and paired wood windows are vertical 1/1-sash.

Individual Resource Status: **Single Dwelling Non-Contributing** Total: 1

610 Dice Street 104-0213-0106



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1910**

July 2006: This extremely well-preserved, 2-story, 2-bay, side-passage-plan, brick dwelling features a hipped roof with cross gables and was constructed ca.1910. The house is laid in 6-course American bond and features a plain brick frieze (like found on other brick houses on 7th Street), gable-end returns, 2/2-sash windows, asphalt shingle roofing, interior flue, overhanging eaves, a transom over the front door, rear shed-roofed porch, and an enclosed shed-roofed basement entry. The fine 3-bay front porch features a hipped roof supported by turned posts, with spindle brackets and plain pickets.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

Individual Resource Status: **Shed** Contributing *Total:* 1

614 Dice Street 104-0213-0105



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1910**

July 2006: This ca. 1910, 3-bay, 2-story, frame I-house features a central-front pedimented gable, stucco siding, standing-seam metal roofing split-level pargeed foundation, a central pargeed flue, slightly overhanging eaves, and a rear 2-story ell with an enclosed 2nd-story side porch. The 3-bayfront porch has turned spindles and modern handrail. The windows and doors have been plyboarded, apparently due to a fire.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

618 Dice Street 104-0213-0104



Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Other, ca 1881**
July 2006: The easternmost three bays of this telescopic, 1-story, stuccoed vernacular dwelling is the original and features a steeply-pitched gable roof with overhanging eaves, 2/2 aluminum windows, a 1-bay pedimented porch, and an exterior-end stuccoed brick-chimney. Constructed ca. 1881, this section has a 1-story, 2-bay gable-roofed wing that projects from its western end. Probably dating to ca. 1900, this section also has aluminum, 2/2-sash windows that match those in the main block. A smaller, more modern, 1-story, 2-bay, hip-roofed stuccoed frame wing extends even further to the west and also features 2/2-sash aluminum windows but of a different size. All walls of this frame building are clad in stucco and the roof in asphalt shingle. *Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1
Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

620 Dice Street 104-0213-0103



Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Other, ca 1890**

July 2006: This ca. 1890, 3-bay, 2-story, frame I-house features a central-front gable, stucco siding, gable-end returns, a transom over the front door, a plain frieze board, 2/2-sash windows, and a rear 2-story wing. The 3-bay front porch has Tuscan columns supports and no balustrade.

Individual Resource Status: **Single Dwelling** Contributing *Total:* 1

Individual Resource Status: **Shed** **Non-Contributing** *Total:* 1

Individual Resource Status: **Shed** **Non-Contributing** *Total:* 1

628 Dice Street 104-0213-0102



Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Other, ca 1984**
July 2006: Constructed in 1984, this 1-story, 3-bay, vernacular frame dwelling is clad in aluminum siding and has a gable roof covered in asphalt shingle. The single and paired windows are 8/8 sash and the house has an exterior-end concrete block flue, split-level foundation, and front entrance deck.

Individual Resource Status: **Single Dwelling Non-Contributing Total: 1**

Individual Resource Status: **Single Dwelling Non-Contributing Total: 1**