

**Elm Street 104-0213-0051**  
*Other DHR Id #: 44AB0527*



*Primary Resource Information:* **Archaeological Site,**

December 2006: Site was visited in Dec. 2006 and portions walked. Substantial piles of brick and other debris were noted but no artifacts were collected. A Sanborn Insurance Map was used to locate former structural features. The site is currently abandoned and grown over in trees and underbrush. A small drainage runs through the west portion of the site. Large mounds of architectural debris (brick, etc.) litter the site.

*Individual Resource Status:* **Archaeological Site**      **Contributing Total: 1**

834, 836 Estes Street 104-0213-0054



*Primary Resource Information:* **Multiple dwelling, Stories 2.00, Style: Other, ca 1895**

July 2006: This 2-story, 2-bay, hip-roofed duplex features a central-cross gable that has been divided by a modern, vertical, concrete block fire wall that has been constructed between the two halves of the building, presumably in order to meet modern fire code. This wall has a parapet roof that extends above the roof line of the building and also projects from the front wall. Each of the apartments has a side entrance with its own 6-bay wraparound porch with square posts. The building, constructed ca. 1895, has been remodeled and is now clad in vinyl siding, with a roof covered in asphalt shingles. The 1/1-sash windows and rear decks are also not original.

*Individual Resource Status:* **Multiple dwelling**      Contributing    *Total:* 1

838, 840 Estes Street 104-0213-0053



*Primary Resource Information:* **Multiple dwelling, Stories 2.00, Style: Other, ca 1895**

July 2006: This 2-story, 2-bay, hip-roofed duplex features a central-cross gable that has been divided by a modern, vertical, concrete block fire wall that has been constructed between the two halves of the building, presumably in order to meet modern fire code. This wall has a parapet roof that extends above the roof line of the building and also projects from the front wall. Each of the apartments has a side entrance with its own 6-bay wraparound porch with square posts. The building, constructed ca. 1895, has been remodeled and is now clad in vinyl siding, with a roof covered in asphalt shingles. The 1/1-sash windows and rear decks are also not original.

*Individual Resource Status:* **Multiple dwelling**      Contributing    *Total:* 1

846 Estes Street 104-0213-0052



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1890**

July 2006: This 2-story, 2-bay, hip and cross-gable-roofed, side-passage-plan, frame dwelling features a hipped roof with cross gables and was constructed ca.1890. The house rests on a parged brick foundation and features a central brick chimney, standing-seam metal roofing, aluminum siding, vinyl 1/1-sash windows, a plain frieze, gable-end returns, a 2-story rear wing, and a rear 1-story gable-roofed wing with enclosed side porch. The 3-bay, hip-roofed front porch is supported by undersized turned spindles and has a balustrade of plain pickets.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

903 Grove Street 104-0213-0040



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1890**  
July 2006: This 2-story, 2-bay, side-passage-plan, frame dwelling has a single window opening centered on the second floor, directly above the window on the first floor. The house has a shed roof clad in standing-seam metal with a Mansard roof on the front that gives the impression of a gable. The walls are clad in vinyl siding and the windows are 6/6-sash. The pedimented, 2-bay front porch has turned posts with turned balusters and gable-end returns. To the rear is a 1-story porch. The house is nearly identical to the one next door at 905 Grove Street (104-213-00390).

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

905 Grove Street 104-0213-0039



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1890**  
July 2006: This 2-story, 2-bay, side-passage-plan, vernacular frame dwelling has a single window opening centered on the second floor, directly above the window on the first floor. The house has a shed roof clad in standing-seam metal with a Mansard roof on the facade. The walls are clad in stucco and the windows are 6/6-sash. The shed-roofed, 2-bay front porch has square posts with lattice between the paired posts. To the rear is a shed-roofed porch. The house is nearly identical to the one next door at 903 Grove Street (104-0213-0040).

*Individual Resource Status:* **Single Dwelling**      Contributing    *Total:* 1

918 Grove Street 104-0213-0245



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1895**  
July 2006: This 2-story, 2-bay, cross-hip-roofed frame dwelling has a projecting front hipped roof and was constructed ca. 1895. The hip-roofed entrance bay is recessed. Clad in vinyl siding and roofed in asphalt shingles, the house features replacement vinyl 1/1-sash windows and vinyl shutters, overhanging eaves, a boxed cornice, and a modern front door with 1-bay entrance porch supported by square posts. To the rear is a 1-story wing with central interior flue and side porch. *Individual Resource Status:* **Single Dwelling**    Contributing    *Total:* 1

920 Grove Street 104-0213-0244



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1895**  
July 2006: Constructed ca. 1895, this 2-story, 2-bay, cross-hip-roofed frame dwelling has a projecting front hip roof. The hip-roofed entrance bay is recessed. Clad in stucco and roofed in asphalt shingles, the house features replacement vinyl 6/6-sash windows with vinyl shutters, overhanging eaves, a boxed cornice with plain friezeboard, and a 2-bay hip-roofed front porch with stuccoed square posts and a solid balustrade. To the rear is a 1-story wing with central interior flue.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1



1000 Grove Street 104-0213-0243



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1895**  
July 2006: This 2-story, 2-bay, hip-roofed, side-passage-plan, frame dwelling was constructed in the early 1890s and features bricktex siding, asphalt shingle roofing, and vinyl 1/1-sash windows, all replacement materials. The 3-light transom, 3-light sidelights, plain freizeboard, central parged chimney, and 3-bay front porch with square posts appear original. To the rear is an ell with a side wing.

*Individual Resource Status:* **Single Dwelling**    Contributing    *Total:* 1  
*Individual Resource Status:* **Shed**                    Contributing    *Total:* 1  
*Individual Resource Status:* **Shed**                    Contributing    *Total:* 1

1002 Grove Street 104-0213-0242



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1895**  
July 2006: Constructed in the early 1890s, this 2-story, 2-bay, cross-gable-roofed, side-passage-plan, frame dwelling features a projecting front cross gable. The asphalt shingle roofing and aluminum siding are replacement materials. The wood 2/2-sash windows, 4-light transom and 2-light sidelights, as well as the 3-bay front porch with square posts and plain pickets, appear original. To the rear is a 1-story gable-roofed wing that is attached to the shed by a breezeway.

*Individual Resource Status:* **Single Dwelling** Contributing Total: 1

*Individual Resource Status:* **Shed** Contributing Total: 1

1004 Grove Street 104-0213-0241



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Queen Anne, ca 1895**

July 2006: This large, 2-story, 4-bay, cross-gable-roofed, side-passage-plan, frame dwelling features a projecting, 2-story, front, cross-gabled, polygonal, Queen Anne-style, cutaway bay. The house, which has recently been rehabilitated is very well preserved and features a raised brick foundation, weatherboard siding, standing-seam metal roofing, a double-leaf front door with 3-light transom of frosted glass, a plain frieze, 2/2-sash wood windows, and a 2-story, 2-level, 1-bay front porch with turned posts. The projecting, polygonal, cut-away front bay features a pedimented gable end with wooden shingles, a rectangular attic vent, and a decorative vergeboard.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1895**  
July 2006: Constructed in the early 1890s, this 2-story, 2-bay, cross-gable-roofed, side-passage-plan, frame dwelling features a projecting front cross gable. The standing-seam metal roof, weatherboard siding, central brick chimney, brick foundation, plain frieze, gable-end returns, and 2-light transom over the door are all original. The windows vary in size and configuration and include 8/8, 2/2 and 1/1-sash. The front door is modern and it appears that the square posts on piers that support the front 3-bay porch are replacements. To the rear is a 1-story gable-roofed wing with an end porch and a side lean-to.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

1008 Grove Street 104-0213-0239



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1895**  
July 2006: Constructed ca. 1895, this 2-story, 2-bay, cross-gable-roofed, side-passage-plan, frame dwelling features an asphalt shingle roof, and asbestos shingle siding, both replacement materials. The vinyl 6/6-sash windows are replacements but the gable-end returns and the exterior brick chimney on the rear are original. The square posts on the 3-bay front porch are replacements but the original turned pilasters are still evident along the wall of the house. It is similar in form to neighboring buildings, 1010 and 1012 Grove Street.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

**1010 Grove Street 104-0213-0238**



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1895**  
July 2006: Constructed ca. 1895, this 2-story, 2-bay, cross-gable-roofed, side-passage-plan, frame dwelling features an asphalt shingle roof, and weatherboard siding. The vinyl 2/2-sash windows are replacements but the gable-end returns, exterior brick chimney on the rear, plain friezeboard, and wooden shingles in the gable ends are original. The 3-bay, hip-roofed, front porch with turned posts has been screened in. The house has a large 1-story rear ell with a shed-roofed lean-to addition. It is similar in form to neighboring buildings, 1012 and 1008 Grove Street.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

*Individual Resource Status:* **Shed** Non-Contributing *Total:* 1

1012 Grove Street 104-0213-0237



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1900**  
July 2006: Constructed ca. 1900, this 2-story, 2-bay, cross-gable-roofed, side-passage-plan, frame dwelling features an asphalt shingle roof, aluminum siding, both replacement materials. The 2/2-sash windows appear original as is does the exterior brick chimney located on the rear of the building. The front door is protected by a gable hood supported by brackets and the house has a 1-story rear wing, as do many of the other houses along this street. It is similar in form to neighboring buildings, 1010 and 1008 Grove Street.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

*Individual Resource Status:* **Shed** **Non-Contributing** *Total:* 1

1013 Grove Street 104-0213-0230



*Primary Resource Information:* **Single Dwelling, Stories 2.50, Style: Other, ca 1925**  
July 2006: This 2½-story, 2-bay, hip-roofed, brick American Foursquare dwelling was constructed ca. 1925. The walls are laid in 6-course American bond with Flemish bond and the house has a standing-seam metal roof with a front hip-roofed dormer that is clad in wood shingles. Architectural details include single and paired 6/1 windows, 3-light sidelights and a 5-light transom around the front door, segmental arches over the openings, overhanging eaves with exposed rafter ends, an interior brick chimney, and a rear 1-story wing. The 2-bay hip-roofed front porch has a wooden floor and Tuscan column supports.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1



1014 Grove Street 104-0213-0236



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1890**

July 2006: This 2-story, 2-bay, gable-end, side-passage-plan, frame dwelling clad in aluminum siding and with an asphalt shingle roof, was constructed in the early 1890s. The house rests on a parged brick foundation and has a central interior brick chimney. Other details include a plain friezeboard, a boxed cornice with gable-end returns, 2/2 windows, a 2-light transom over the door, and a rear 1-story wing. The 3-bay, hip-roofed front porch has a concrete floor and is supported by chamfered posts with sawn brackets.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

*Individual Resource Status:* **Shed** **Non-Contributing** *Total:* 1

1015 Grove Street 104-0213-0229



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1890**  
July 2006: This 2-story, 2-bay, cross-gable-roofed, side-passage-plan, frame dwelling features an asphalt shingle roof and was constructed in the early 1890s. The house, which is clad in weatherboard siding, rests on a parged foundation and is missing its chimney. Other details include a plain friezeboard, gable-end returns, modern vinyl 1/1 windows, a single transom over the front doors, and a rear 1-story wing. The 3-bay hip-roofed front porch has the original standing-seam metal roofing and chamfered supports.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

1016 Grove Street 104-0213-0235



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1900**  
July 2006: This 2-story, 2-bay, cross-gable-roofed, side-passage-plan, frame dwelling features an asphalt shingle roof and was constructed in the early 1900s. The house, which is clad in weatherboard siding, rests on a parged foundation and has a central interior brick chimney. Other details include a plain friezeboard, gable-end returns, 2/6 windows, a polygonal bay window with 1/1 windows on the first floor, and a rear 2-story ell with side shed-roofed wing. The 2-bay, hip-roofed front porch has chamfered posts, and small brackets, and covers the front door that is surmounted by a 2-light transom.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

1017 Grove Street 104-0213-0228



*Primary Resource Information:* **Apartment Building, Stories 1.00, Style: Other, ca 1972**

July 2006: This 1-story, gable-end, 8-unit brick apartment building was constructed ca. 1972 and features 4 bays on each side fronted by integral porches.

*Individual Resource Status:* **Apartment Building**      **Non-Contributing**      *Total:1*

1018 Grove Street 104-0213-0234



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 2003**  
July 2006: Constructed ca. 2003, this 2-story, 3-bay, gable-end, frame dwelling is clad in Hardi-plank and contains an integral 2-bay front porch with turned posts. The roofing is asphalt shingle and the windows are square 4-light sash and banked 4/1-sash. A rear 2-story gable-roofed wing is taller than the front section.

*Individual Resource Status:* **Single Dwelling Non-Contributing** Total: 1

1020 Grove Street 104-0213-0233



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1890**  
July 2006: This 2-story, 2-bay, side-passage-plan, gable-end, vernacular frame dwelling has a single window opening centered on the second floor, directly above the window on the first floor. Constructed ca. 1891, the house has a gable-end roof clad in standing-seam metal, and the walls are clad in aluminum siding. The exterior brick chimney located at the rear end of the gable is partially enclosed because of the rear 1-story wing that has been remodeled and enlarged with a side lean-to wing. This simply trimmed house has original 6/6-sash windows and a 2-bay, shed-roofed front porch with square posts. The brick pier foundation has concrete block infill.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

1021 Grove Street 104-0213-0227



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1910**  
July 2006: A 2-story, 2-bay, hip-roofed dwelling constructed ca. 1910, this vernacular hip-roofed house is clad in weatherboard siding with a roof covered in standing-seam metal. Almost identical to the house next door (1023 Grove), architectural details include a plain frieze, 3-light transom and 3-light sidelights, corner boards, interior brick chimney, a boxed cornice, 2/2-sash wood windows, brick foundation, 2-story rear ell, and modern vinyl shutters. The 2-bay, hip-roofed front porch has turned posts, exposed rafter ends, and turned balusters. A 1-story enclosed porch extends off the side of the ell.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

**\*1022 Grove Street 104-0245**  
*Other DHR Id #: 104-0213-0232*



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1891**  
July 2006: Listed on the National Register of Historic Places as part of the Charlottesville Multiple Resource Area District, this worker's cottage is also an Individually Protected historic property within the City of Charlottesville. The 2-story, 2-bay, side-passage-plan, gable-end, vernacular frame dwelling has a single window opening centered on the second floor, directly above the window on the first floor. Constructed in 1891 by James A. Gardner, the house has a gable-end roof clad in standing-seam metal, and the walls are clad in stucco. The exterior brick chimney located at the rear end of the gable is partially enclosed because of the rear 1-story wing. This simply trimmed house has original 6/6-sash windows and a 2-bay, shed-roofed front porch with square posts and a 4-rail balustrade along the side.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1



1023 Grove Street 104-0213-0226



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1910**  
July 2006: A 2-story, 2-bay, hip-roofed dwelling constructed ca. 1910, this vernacular hip-roofed house is clad in weatherboard siding with a roof covered in standing-seam metal. Almost identical to the house next door (1021 Grove), architectural details include a plain frieze, corner boards, interior brick chimney, a boxed cornice, 2/2-sash wood windows, brick foundation, 2-story rear ell, and modern vinyl shutters. The 2-bay, hip-roofed front porch has turned posts, exposed rafter ends, and turned balusters. A 1-story enclosed porch extends off the side of the ell.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

1024 Grove Street 104-0213-0231



July 2006: This 2-story, 2-bay, gable-roofed, vernacular, late-19th-century, frame dwelling rests on a parged foundation. The walls are clad in stucco and the house features an exterior brick chimney on the rear that is now partially enclosed because of a rear 1-story wing. Other details include asphalt shingle roofing, a single transom over the door, overhanging eaves, modern vinyl 1/1 windows, and a 3-bay, hip-roofed front porch with square posts.

*Individual Resource Status: **Single Dwelling** Contributing Total: 1*

1025 Grove Street 104-0213-0225



*Primary Resource Information:* **Single Dwelling, Stories 1.00, Style: Other, ca 1971**  
July 2006: This 1-story, 3-bay, vernacular dwelling was constructed ca. 1971 and features a raised concrete block foundation, 1/1 windows, aluminum siding, and an asphalt shingled gable roof.

*Individual Resource Status:* **Single Dwelling Non-Contributing Total: 1**

1027 Grove Street 104-0213-0224



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1890**

July 2006: This 2-story, 2-bay, side-passage-plan, frame dwelling has a single window opening centered on the second floor, directly above the window on the first floor. The house has a gable-end roof of standing-seam metal, with an exterior-end brick chimney, brick foundation, weatherboard siding with cornerboards, and 6/6-sash windows. The 3-bay front porch has turned posts and plain pickets. A 1-story, 1-bay, gable-roofed frame wing extends to the west and appears original. To the rear is a shed-roofed wing.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

761 King Street 104-0213-0078



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1900**

July 2006: A 2-story, 2-bay, hip-roofed dwelling constructed ca. 1900, this vernacular side-passage-plan house is clad in vinyl siding with a roof covered in asphalt shingles. Resting on a brick foundation, the house features a 3-bay, hip-roofed front porch with turned posts and balusters, modern vinyl 6/6-sash windows, a side 1-story wing, and a rear 1-story wing.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

763 King Street 104-0213-0079



*Primary Resource Information:* **Single Dwelling, Stories 1.00, Style: Other, ca 1940**  
July 2006: Constructed ca. 1940, this 1-story, 3-bay, vernacular frame dwelling is fairly well-preserved. The gable roof is clad in asphalt shingle and the frame walls in weatherboard siding. The 6/6-sash windows appear original as does the central brick flue, and the 1-bay shed-roofed front porch with turned posts.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

765 King Street 104-0213-0080



*Primary Resource Information:* **Single Dwelling, Stories 1.00, Style: Other, ca 1940**  
July 2006: Constructed ca. 1940, this 1-story, 3-bay, vernacular frame dwelling is clad in vinyl siding with an asphalt shingled gable roof. The house rests on a concrete block foundation and features 6/1 wood windows, a central brick chimney, and a 1-bay gabled front porch with paired square posts.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

811 King Street 104-0213-0081



*Primary Resource Information:* **Single Dwelling, Stories 1.00, Style: Other, ca 1953**  
July 2006: Constructed ca. 1953, this 1-story, 3-bay, vernacular frame dwelling is clad in asbestos shingle siding with an asphalt shingled gable roof. The house rests on a concrete block foundation and features 1/1 wood windows, a 3-part bay window, a central concrete block flue, and a shed roof over the entrance.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1



813 King Street 104-0213-0082



*Primary Resource Information:* **Single Dwelling, Stories 1.00, Style: Other, ca 1953**  
July 2006: Constructed ca. 1953, this 1-story, 3-bay, gable-end, vernacular frame dwelling is clad in asbestos shingle siding with an asphalt shingled gable roof. The house rests on a concrete block foundation and features 1/1 wood windows, a 3-part bay window, a central concrete block flue, and a 2-bay gabled entry porch with modern square posts.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

815 King Street 104-0213-0083



*Primary Resource Information:* **Single Dwelling, Stories 1.00, Style: Other, ca 1953**  
July 2006: Constructed ca. 1953, this 1-story, 3-bay, gable-roofed, vernacular frame dwelling is clad in asbestos shingle siding with an asphalt shingled gable roof. The house rests on a concrete block parged foundation and features 8/8 wood windows, a central concrete block flue, and cottage-style multi-light front door, and a 1-bay pedimented entry porch with square posts as supports.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

821 King Street 104-0213-0084



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1900**

July 2006: This ca. 1900, 2-story, 2-bay, vernacular frame dwelling is currently abandoned with the window and door covered with plywood. The side-passage-plan dwelling features an asphalt shingle roof, asbestos shingle siding, a brick foundation, a plain friezeboard, gable-end returns, a central brick chimney, and a rectangular louvered front attic vent. The 3-bay, hip-roofed front porch has square posts and a solid balustrade covered in siding creating segmental-arched bays.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

909 King Street 104-0213-0246



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1900**  
July 2006: This 2-story, 2-bay, gable-end, side-passage-plan, vernacular frame dwelling has a single window opening centered on the second floor, which lines up with the window on the first floor. The house has an asphalt shingled roof, the walls are clad in aluminum siding, and the vinyl 6/6-sash windows, and modern front door are replacements. A large exterior-end rear brick chimney is now enclosed because of a rear 2-story wing. An enclosed shed-roofed porch runs the length of the house along the west side. The split-level foundation is of brick with an entry along the east side. The front, 1-bay, shed roofed porch has square posts and a modern balustrade.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

*Individual Resource Status:* **Shed** **Non-Contributing** *Total:* 1

910 King Street 104-0213-0264



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1900**  
July 2006: This unique, 2-story, 3-bay, cross-gable-roofed, vernacular frame dwelling has the unusual feature of a diagonal entrance bay at the junction of the two wings. The 2-story angled wall has a pedimented gable end and a 1-story, 3-bay polygonal entry porch with square posts and sawn brackets. The late-19th-century house rests on a split-level brick foundation, the walls are clad in asbestos shingle, and the roof is covered in standing-seam metal. Other details include a plain frieze, gable end returns, an interior-end brick chimney on the east wing, a central brick chimney on the west wing, 2/2-sash wood windows, and a rear 1-story wing.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1  
*Individual Resource Status:* **Garage** Contributing *Total:* 1

913 King Street 104-0213-0247



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1900**  
July 2006: This late-19th-century, 2-story, 2-bay, hip-roofed, vernacular frame dwelling has a projecting front hipped roof and a recessed gable-end entrance bay. Clad in aluminum siding and roofed in asphalt shingles, the house features 2/2-sash wood windows, some replacement vinyl 1/1-sash windows, a large central brick chimney, a parged foundation, a modern door with enclosed single-light transom, gable-end returns, overhanging eaves, and a rear 1-story wing. The front 2-bay front porch has square posts as supports although the original turned pilasters still survive.

*Individual Resource Status:* **Single Dwelling**      Contributing    *Total:* 1

915, 917 King Street 104-0213-0248



*Primary Resource Information:* **Single Dwelling, Stories 1.50, Style: Colonial Revival, ca 1946**

July 2006: This ca. 1946, 1½-story, 3-bay, frame dwelling features a gable roof with two gabled front dormers and a large rear dormer. Of the Cape Cod- form, the house is clad in aluminum siding, and the roof is covered in asphalt shingles. It contains 6/6- and 8/8-sash wood windows, vinyl shutters, an exterior-end brick chimney (clad in aluminum siding), and fluted Colonial Revival-style trim around the front door. Concrete steps with metal railing lead up to a front stoop with an aluminum awning. To the side is a large deck with metal balustrade.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

916 King Street 104-0213-0263



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1900**  
July 2006: This 2-story, 2-bay, side-passage-plan, gable-end, vernacular frame dwelling has a single window opening centered on the second floor, which lines up with the window on the first floor. Constructed ca. 1900, the house has a gable-end roof clad in asphalt shingles and walls clad in rectangular asphalt shingles. The exterior brick chimney located at the rear end of the gable is enclosed because of a rear 2-story wing. A 1-story rear shed-roofed wing extends off the end and side of the 2-story wing. The windows are 1/1-sash and the front, 2-bay hip-roofed porch has square posts.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1



918 King Street 104-0213-0262



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1900**  
July 2006: This ca. 1900, 2-story, 2-bay, gable-end, side-passage-plan, frame dwelling is clad in aluminum siding and roofed in standing-seam metal. To the rear is an exterior brick chimney that is enclosed because of a rear 2-story wing. Off the rear of this wing is a modern 1-story addition that wraps around the side of the house. The 6/6-sash windows and overhanging eaves appear original as does the roof of the 2-bay front porch, which has modern metal supports.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

*Individual Resource Status:* **Single Dwelling Non-Contributing** *Total:* 1

**920 King Street 104-0213-0261**



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1900**  
July 2006: This well-preserved, late-19th-century, 2-story, 2-bay, hip-roofed, side-passage-plan, frame dwelling appears to be vacant. It features Bricktex siding, a standing-seam metal roof, original 2/2-sash wood windows, a brick pier foundation with concrete infill, and a plain frieze with brackets. An exterior brick chimney is located along the rear wall and other details include a transom over the 4-paneled door, overhanging eaves, a rear 1-story wing, and a 2-bay, hip-roofed front porch with chamfered posts on wood piers and a concrete floor.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

922 King Street 104-0213-0260



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1900**

July 2006: This late-19th-century, 2-story, 2-bay, hip-roofed, side-passage-plan, frame dwelling features stucco siding, asphalt shingle roofing, original 2/2-sash wood windows on the second floor and 1/1-sash vinyl windows on the first floor. Other details include a parged foundation, an exterior parged brick chimney along the rear wall, a transom over the door, a plain frieze, and a side and rear 1-story wing. The 2-bay, hip-roofed front porch has chamfered posts on wood piers, sawn brackets, plain pickets, a denticulated frieze, and a concrete floor.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

*Individual Resource Status:* **Shed** Non-Contributing *Total:* 1

924 King Street 104-0213-0259



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1900**  
July 2006: This turn-of-the-century, 2-story, 3-bay, vernacular frame dwelling has receding bays from left to right. The narrowest of the three bays is the center entrance bay. The house is clad in vinyl siding with a tongue-and-groove wide wooden frieze with brackets. The 2/2-sash windows on the second floor are vinyl replacements, while the 1/1-sashes on the first floor are wooden. A transom is located over the front door. A 3-bay, shed-roofed porch unites the central and right bays and has chamfered posts and sawn brackets. The house appears to have been remodeled and currently a large 2-story addition is being constructed to the rear.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

*Individual Resource Status:* **Shed** Non-Contributing *Total:* 1

926 King Street 104-0213-0258



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1900**  
July 2006: This ca. 1900, 2-story, 2-bay, gable-roofed, side-passage-plan, vernacular frame dwelling is clad in vinyl siding, with a standing-seam metal roof, double-hung 6/6-sash windows, and a brick foundation. The main chimney appears to be missing and the house has a large 1-story, hip-roofed rear wing with shed addition. Other details include overhanging eaves, a transom over the front door and a 3-bay hip-roofed front porch with turned posts and plain pickets.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

928 King Street 104-0213-0257



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1900**  
July 2006: This ca. 1900, 2-story, 2-bay, hip-roofed, side-passage-plan, vernacular frame dwelling is clad in vinyl siding, with an asphalt shingled roof, and vinyl 1/1-sash windows with vinyl shutters, all replacement materials. The main chimney appears to be missing and the house has a large rear 1-story wing with interior flues. The house features overhanging eaves and a 3-bay, hip-roofed front porch with turned posts.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

1000 King Street 104-0213-0256



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1900**  
July 2006: This 2-story, 2-bay, cross-gable-roofed, side-passage-plan, frame dwelling features an asphalt shingled roof and stucco siding. Constructed during the early 20th century, the entrance bay is recessed with a projecting front cross gable. The house rests on a parged foundation and is missing its chimney. Other details include a plain friezeboard, 2/2-sash wood windows, an enclosed transom and sidelights around the front door, and a rear 2-story ell with two 1-story wings off it. The 3-bay hip-roofed front porch has turned spindles and plain pickets.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

**1001 King Street 104-0213-0249**



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1940**  
July 2006: This ca. 1940, 1-story, 3-bay, frame vernacular dwelling features a gable roof of standing-seam metal with a central brick flue. To the west is a 1-bay gable-roofed wing that is slightly set back from the main block. The stuccoed house contains 6/6-sash wood windows, exposed rafter ends, and a lean-to rear wing. The 1-bay, gabled front porch features square posts, exposed rafter ends and a concrete stoop.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1



1002 King Street 104-0213-0255



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1900**  
July 2006: This well-preserved, 2-story, 2-bay, cross-gable-roofed, side-passage-plan, frame dwelling features a standing-seam metal roof and vinyl siding. Constructed during the late 19th century, the house rests on a parged brick foundation and has an exterior brick chimney along the rear side gable, a plain friezeboard, gable-end returns, 2/2-sash wood windows with vinyl shutters, round wooden attic vents in the gable ends, and a transom and sidelights around the front door. To the rear is a 1-story wing and deck. The front 3-bay, hip-roofed porch has turned posts, a spindle frieze, and a balustrade of plain pickets.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

1004 King Street 104-0213-0254



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1905**  
July 2006: This early-20th-century, 2-story, 2-bay, cross-gable-roofed, side-passage-plan, frame dwelling features an asphalt shingle roof and stucco siding. The house, which is clad in vinyl siding, rests on a brick foundation and has an interior brick chimney, a plain friezeboard, gable-end returns, modern vinyl 1/1 windows, round wooden attic vents in the gable ends, and a transom and sidelights around the front door. To the rear are a 2-story ell and a 1-story wing. The front 3-bay, hip-roofed porch has square posts and a concrete pad.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

*Individual Resource Status:* **Shed** Non-Contributing *Total:* 1

1015 King Street 104-0213-0250



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1890**

July 2006: This 2-story, 2-bay, side-passage-plan, frame dwelling has a single window opening on the second floor, which lines up with the window on the first floor.

Constructed ca. 1890, the gable-roofed frame house is clad in aluminum siding with a standing-seam metal roof. The 2/2-sash windows, exterior-end brick chimney, 2-light transom over the door and side 1-story wing are original. The 2-bay hip-roofed front porch has chamfered posts and modern metal railing. To the rear is a 1-story enclosed porch. The house is nearly identical to the one next door at 1017 King Street (104-0213-0251).

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

*Individual Resource Status:* **Shed** **Non-Contributing** *Total:* 1

1017 King Street 104-0213-0251



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1890**  
July 2006: This 2-story, 2-bay, side-passage-plan, frame dwelling has a single window opening on the second floor, which lines up with the window on the first floor. Constructed ca. 1890, the gable-roofed frame house is clad in vinyl siding with an asphalt shingled roof, and modern 1/1-sash vinyl windows. Other details include an exterior-end brick chimney, a 2-light transom over the door, a rear shed-roofed 1-story wing, and a 2-bay hip-roofed front porch with modern iron supports. One bay of the side 1-story wing appears original, with the second bay added at a later time. The house is nearly identical to the one next door at 1015 King Street (104-0213-0250).

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

1021 King Street 104-0213-0252



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1905**  
July 2006: This 2-story, 2-bay, side-passage-plan, vernacular frame dwelling has a single window opening centered on the second floor, which lines up with the window on the first floor. Constructed ca. 1905, the house has a gable-end roof clad in asphalt shingles and walls clad in stucco. The exterior brick chimney located at the rear end of the gable is partially enclosed because of the rear 1-story wing that has been remodeled and enlarged with a side lean-to wing. This simply trimmed house has original 6/6-sash windows, a parged foundation, a side 1-story shed-roofed modern wing with entrance, and a shed-roofed enclosed front porch.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1

1023 King Street 104-0213-0253



*Primary Resource Information:* **Single Dwelling, Stories 2.00, Style: Other, ca 1905**  
July 2006: This 2-story, 2-bay, cross-gable-roofed, side-passage-plan, frame dwelling features an asphalt shingle roof and was constructed around the turn-of-the-century. The house, which is clad in vinyl siding, rests on a parged foundation and has an interior brick chimney with a plain cap. Other details include a plain friezeboard, gable-end returns, modern single and paired vinyl 1/1 windows, a side 1-story modern wing, and several rear 1-story wings. The 3-bay hip-roofed front porch has square posts and plain pickets.

*Individual Resource Status:* **Single Dwelling** Contributing *Total:* 1